

----- CHASSIS -----

CHASSIS: 100" W KME PREDATOR PANTHER
 CAB: MFD WITH 10" RAISED ROOF
 ENGINE: CUMMINS ISL9 450 HP
 TRANSMISSION: ALLISON 3000EVS
 FRONT AXLE: 20,000 LBS
 REAR AXLE: 27,000 LBS

----- PUMP -----

PUMP: HALE QMAX-175 1750 SINGLE STAGE
 INTAKES
 DRIVER SIDE: 6" & 3"
 OFFICER SIDE: 6" & 3"
 FRONT: N/A
 REAR: 5"
 DISCHARGES
 DRIVER SIDE: (1) 4" & (1) 3"
 OFFICER SIDE: (1) 4" & (1) 3"
 FRONT: (1) 1 1/2" DS
 REAR: (2) 3" DS
 DECK GUN: (1) 3"
 OTHER: (2) 1 3/4" SPEEDLAYS
 (1) 2 1/2" CROSSLAY

----- TANK -----

TANK: POLY
 WATER: 990 GALLONS
 FOAM: N/A
 EXTRA FILLS: F-FRIEND REAR
 DUMPS: N/A

----- BODY -----

BODY TYPE: 158" FLEX MEDIUM
 MATERIAL: 3/16" ALUMINUM
 COMPARTMENTATION
 DRIVER SIDE: FULL HEIGHT/SPLIT DEPTH
 OFFICER SIDE: FULL HEIGHT/SPLIT DEPTH
 HOSEBED
 DIVIDERS: ONE (1)
 HOSE LOAD: MIN

----- MISC. -----

GENERATOR: ONAN PTO/HYD 10,000 WATT
 FOAM SYSTEM: N/A

CUSTOMER APPROVAL:

NAME: _____
 TITLE: _____
 DATE: _____

THIS DRAWING IS A GENERAL CONFIGURATION AND MAY NOT NECESSARILY REFLECT ALL CONTRACTUAL REQUIREMENTS. CONTRACT SPECIFICATIONS SHALL PREVAIL OVER DRAWING

05/11/16	AS BUILT	RPS
SYM	DATE	REVISION DESCRIPTION

SALES ENGINEER : SHAWN McARDLE



KOVATCH MOBILE EQUIPMENT
 ONE INDUSTRIAL COMPLEX - NESQUEHONING, PA 18240

DIMENSIONS ARE APPROXIMATE & MAY VARY DUE TO BUILD ADJUSTMENTS
 DATE: 05/11/2016 SCALE: 1"=24" DWG SIZE: D DRAWN BY: JMD APPROVED BY: SM

KME CUSTOM PUMPER
 BOWMANVILLE FC, PA
 GSO#10083

